

Sklar Completes Smackover Wildcat In Conecuh County

Sklar Exploration Co., LLC, Shreveport, La., has completed in Smackover at a wildcat northeast of Little Cedar Creek Field in southern Alabama's Conecuh County.

The No. 1 Craft-Mack 7-2, NW NE Section 7-4N-13E, was completed flowing 73 barrels 43.3-gravity oil and 63,000 cubic feet of gas per day through a 14/64-inch choke with flowing tubing pressure 200 pounds.

Completion was from pay in Smackover through perforations 11,070-102 feet. Total depth is 11,300 feet and 5 1/2-inch casing was run to bottom. The producing zone was acidized prior to completion.

Rapad Drilling Co., Jackson, Miss., handled contract.

Site of the new production is five-eighths of a mile north-northeast of

the nearest completed producer in Little Cedar Creek Field.

Five-eighths of a mile southwest of the completion, Midroc Operating Co. completed No. 7-11 McCreary, NE SW Section 7-4N-13E. Productive from pay in Smackover, the well flowed 164 barrels 46-gravity oil and 152,000 cubic feet of gas per day. Completion was from perforations 11,220-242 feet.

Drilled to 11,570 feet, pay was logged in two zones of Smackover and string of 5 1/2-inch casing was run to total depth.

Seven-eighths of a mile northeast of the No. 1 Craft-Mack 7-2, meantime, Sklar is waiting on completion rig at No. 1 Craft-Cedar Creek Land & Timber, Inc. 5-5, SW NW Section 5-4N-13E. It was drilled to 11,200 feet. Shows were logged in Smackover and 5 1/2-inch casing was run to 11,193 feet for evaluation.